

Replacement Multi-family house, Dübendorf



Timbatec was responsible for the timber construction, timber statics and fire protection in the apartment building. From the first floor upwards, everything including the staircase was built in timber.

The project

The apartment building in Dübendorf has a basement in reinforced concrete and 5 floors above in wood with a wooden staircase. There are a total of 5 apartments in the building on the ground and upper floors. The basement only contains cellars and technical rooms. The facade is partly covered with PV modules and horizontal timber cladding.

The construction method

The walls are of frame construction and the floor slabs are constructed with horizontal glulam. The stairwell and the bracing walls are constructed with cross-laminated timber walls.

The challenge

It was a challenge to find a suitable bracing system, as the floor plan is very compact in relation to the height and the walls are correspondingly short. This was solved with cross-laminated timber walls, which were braced with threaded rods.



Services of Timbatec

- SIA Phase 32 Bauprojekt
- SIA Phase 41 Ausschreibung und Offertenvergleich
- SIA Phase 51 Ausführungsprojekt
- Brandschutz Qualitätssicherung QSS2

Holzbauingenieur

Timbatec Holzbauingenieure (Schweiz) AG Zürich
8005 Zürich

Holzbau

Flück Holzbau AG
8602 Wangen

Fotografie

kämpfen zinke + partner ag
8055 Zürich

Auftraggeber

kämpfen zinke + partner ag
8055 Zürich